

## Nancy Creek Pump Station Shaft Atlanta, GA



### PROJECT OVERVIEW AND CHALLENGES

The City of Atlanta awarded a design-build contract to Western Summit Constructors, Inc. (WSCI) to construct a 100 mgd, 160' deep pump station at the R.M. Clayton WWTP. WSCI hired Bradshaw/Frontier Kemper JV (BFK) to design, excavate and support the shaft for the pump station. Jenny Engineering designed the shaft for BFK. The shaft was 72' in diameter by 150 feet deep after site excavation. The upper 60' was in residual piedmont soil and partially weather rock and supported with lattice girders, wire mesh & shotcrete. The lower 90' was in mica schist & gneiss & supported primarily with spot rock bolts and locally with wire mesh and shotcrete. BFK completed the shaft in 5.5 months. The project earned a 2006 Design-Build Excellence Award from the DBIA.



### PROJECT INFORMATION - 419

**OWNER:**

City of Atlanta  
Scott Miller  
404.597.2643

**ENGINEER:**

Jenny Engineering  
Prakash Donde  
973.379.6699

**CONTRACTOR:**

Western Summit Constructors

**COMPLETION DATE:**

7/20/2004

**GEOLOGY:**

Residual Soils, Mica Schist

**EXCAVATION METHOD:**

SEM/NATM Soft Ground  
Drill & Blast Rock

**MINING DIMENSIONS:**

72' Ø x 150VF

**FINAL LINING:**

N/A

**FOR MORE INFORMATION:**

Eric Eisold, Vice President  
410.970.8300  
eeisold@bradshawcc.com  
Refer to Project 419